

BSS-2000 Embedded Synthetic Track Surfacing System System Specifications

Part 1 – General

1.1 – Scope

*The synthetic surfacing contractor shall furnish all labor, materials, equipment, supervision and services necessary for the proper completion of the **BSS-2000 Dual Durometer** synthetic track surfacing and related work indicated on the drawings and specified herein.*

The synthetic surfacing contractor shall refer to the drawings for the required locations of synthetic track surfacing to be installed. All quantities and dimensions shall be field verified by the synthetic surfacing contractor.

1.2 – Specific Scope of Work

- A. Install a full depth poured-in-place two component, UV stabilized elastomeric polyurethane Dual Durometer synthetic surfacing system with embedded textured finish that has been Class I Certified by the IAAF.***
- B. Layout and paint all track lines and event markings as required and specified by current IAAF and NCAA rules.***

1.3 - Coordination

The synthetic surfacing contractor shall coordinate the work specified with an authorized and appointed representative of the owner so as to perform the work during a period and in a manner acceptable to the owner.

Part 2 – Codes and Standards

2.1 – Applicable Publications

Codes and standards follow the current guidelines set forth by the International Amateur Athletic Federation (IAAF) and the National Collegiate Athletic Association (NCAA), along with the current material testing guidelines as published by the American Society of Testing and Materials (ASTM).

2.2 – Performance Standards

The new synthetic track surfacing system shall exhibit the following minimum performance standards as required by IAAF:

A. Thickness	Average - ≥ 12 mm Minimum - 10mm
B. Force Reduction	35 to 50
C. Modified Vertical Deformation	0.6 to 1.8
D. Friction: TRRL Skid Resistance	≥ 47
E. Tensile Strength	≥ 0.5
F. Elongation at break	≥ 40

Part 3 - Quality Assurance

3.1 – Contractor Qualifications

- A. *The CONTRACTOR must have a minimum of 5 years of experience in the installation of full depth poured-in-place two component elastomeric polyurethane synthetic track surfacing.*
- B. *The MANUFACTURER and CONTRACTOR shall be the same and must have a minimum of 10 years of experience with the compounding of two-part polyurethane for athletic surfaces.*
- C. *The INSTALLATION SUPERVISOR must have installed a minimum of 5 full depth two component polyurethane tracks with embedded texture in the last 3 years. A reference list must be submitted.*
- D. *The INSTALLATION SUPERVISOR must have installed an IAAF Class I Certified running track.*

3.2 – Submittals

The following submittals must be received with bid submittal:

- A. *Standard printed specifications of the synthetic track surfacing system to be installed on this project.*
- B. *An affidavit attesting that the synthetic track surfacing material to be installed meets the requirements defined by the manufacturers currently published specifications and any modifications outlined in those technical specifications.*
- C. *A synthetic track surfacing system sample, 12” x 12” in size, of the same synthetic track surfacing system to be installed on this project.*

- D. *A list of completed facilities, including the installing supervisor, of the exact Dual Durometer synthetic track surfacing system.*
- E. *Test results from an approved IAAF Testing Laboratory confirming compliance to the performance of athletic tracks test according to the IAAF.*

Part 4 – Materials

4.1 – Elastomeric Polyurethane

- A. *BEYPUR, the two-component U.V. stabilized elastomeric polyurethane compounded from polyol and isocyanate components, based on one hundred percent Methylene Diphenyl Isocyanate (MDI). No Toluene Diisocyanate Isocyanate (TDI) will be allowed.*
- B. *The elastomeric polyurethane shall be red in color.*

4.2 – EPDM Granulate

- A. *The EPDM granulates shall be 1 to 3mm in size and peroxide cured.*
- B. *The EPDM granulates and the U.V. stabilized elastomeric polyurethane shall be color matched.*

4.3 – Rubber Granulate

- A. *Red butyl rubber processed ground to a graded size not to exceed .5 – 1mm.*
- B. *A maximum of twenty percent, by weight, of the butyl rubber will be allowed in the force reduction layer.*

4.6 – Line Marking Paint

- A. *Single-component, moisture cured, aliphatic polyurethane paint.*

Part 5 – Installation

5.1 – Subbase

The synthetic track surfacing system shall be laid on an approved subbase. The General Contractor shall provide compaction test results of 95% or greater for the installed subbase and asphalt surface.

For NCAA and IAAF certification the following criteria must be followed: The track surface, i.e. asphalt substrate, shall not vary from planned cross slope by more than .1% with a maximum lateral scope outside to inside of 1% and maximum slope of 0.1% in any running direction. The finished asphalt shall not vary under a 10' straightedge more than 1/8".

It should be the responsibility of the asphalt paving contractor to flood the surface immediately after the asphalt is capable of handling traffic, but within 24 hours. If, after 20 minutes of drying time, there are birdbaths evident, it shall be the responsibility of the architect, in conjunction with the surfacing contractor, to determine the method of correction. No cold tar patching, skin patching or sand mix patching will be acceptable.

Any oil spills (hydraulic, diesel, motor oil, etc.) must be completely removed and replaced with either polyurethane or new, keyed in asphalt. The minimum curing time for the asphalt base is 28 days. It shall be the responsibility of the surfacing contractor to determine if the asphalt substrate has cured sufficiently prior to the application of the polyurethane surfacing system.

It shall be the responsibility of the general contractor to determine if the asphalt substrate meets all design specifications, i.e. cross slopes, planarity and specific project criteria. After all the above conditions are met, the synthetic surfacing contractor must, in writing, accept the planarity of the asphalt receiving base, before work can commence.

5.2 – Thickness

*Total thickness of the **BSS-2000 Dual Durometer Embedded** synthetic track surfacing system shall average 13mm.*

5.3 – Equipment

*The **BSS-2000 Dual Durometer Embedded** synthetic track surfacing system components shall be processed and installed by specially designed machinery with automatic electronic portioning, which provides continuous mixing, feeding and finishing for accurate quality controlled installation.*

No hand mixing will be allowed.

5.4 – Materials

A. Force Reduction Layer

The red butyl granules and UV stabilized elastomeric polyurethane shall be metered and mixed together on site to regulate the ratio/quantity of

butyl, not to exceed fourteen percent in the system and to insure an even distribution of the granules throughout the 8mm force reduction layer. No multi-layered system allowed.

B. Resilient Wearing Layer

The 1 to 3 millimeter EPDM granules shall be mechanically integrated with an UV stabilized elastomeric polyurethane to the full depth of the 5mm wearing layer. The resilient textured finish shall be a dense matrix of embedded EPDM granules.

5.5 – Site Conditions

- A.** *Installation shall not take place if adjacent or concurrent construction generates excessive dust, abrasives or any other byproduct that, in the opinion of the installer, would be harmful to the track material, until completion of such works.*
- B.** *If, in the opinion of the installer of the synthetic material, the weather and/or climatic conditions are detrimental to the proper installation of the surfacing materials, work shall be delayed until conditions are acceptable. Preferred installed temperature is 50 degrees Fahrenheit and rising. Installation shall be executed only in dry conditions.*

Part 6 – Line Striping and Event Markings

6.1 – Layout

Line striping and event markings shall be laid out in accordance with current IAAF and NCAA rules.

6.2 – Certification

Upon completion of the installation, the owner shall be supplied with all necessary computations and drawings as well as a letter of certification attesting to the accuracy of the markings.

Part 7 – Guarantee

Synthetic track surfacing system shall be fully guaranteed against faulty workmanship and material failure for a period of ten (10) years from the date of acceptance.

Additionally, the CONTRACTOR will restripe the track one (1) time during the warranty period at no cost to the owner.

Synthetic surfacing material found to be defective as a result of faulty workmanship and/or material failure shall be replaced or repaired at no charge, upon written notification within the guarantee period.